

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>30</u> N. <u>6</u> W.	A-1; A-3; E-3
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 2, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 1 Reestablished corner on third correction line, common to T30N, R6&7W, at prorated distance E & W for 2½ miles; east 2 miles to corner to Sec. 4 & 5, T30N, R6W, to Hebden dependent resurvey of 1877 & west ½ mile to SW Sec. 31, T31N, R6W to US resurvey of T30N, R7W, of 1855. The corner is on line between the S¼ & SE corners of Sec. 31, T31N, R6W. The S¼ corner of Sec. 31, T31N, R6W, is N89°16' W, 127.28'.
- 3 Reestablished corner in N-S fence and at prorated distance to Hebden for 1 mile north and 1½ miles south. The position in the N-S fence fits Hebden distance E one mile within 2 ft.
- 3 Department monument as set in 1961 at position of recovered corner and Hebden 1877 N.B.T. Stumps of both U.S.B.T.'s also in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1	A-3	E-3
Set DNR mon. & cedar post	Set DNR mon. & cedar post	Found DNR mon. & cedar post
5" Maple N32°E 29.6	5" Ironwood Due N 1.0	10" Cedar N32°E 12.7
6" Maple S40°E 23.5	5" Ironwood S15°E 14.6	9" Cedar S61°E 15.6
6" Maple S50°W 23.0	7" Maple S24°W 18.1	10" Cedar S17°E 12.8
6" Maple N29°W 29.3	5" Maple N86°W 14.4	9" Cedar N80°W 17.6
E-W Random Due S 89'		

SIGNED BY Carl F. Roser 9-15-76 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CHESTONIA TOWNSHIP
ANTRIM COUNTY