

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 30 N. R. 6W


Antrim COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 5-8

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11-20-61

WITNESSES TO CORNER.....



6" Cedar - S 2 W - 22.2 feet

6" Cedar - S 88 W - 15.0 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township.
Restored corner from Hebdon's NE cedar witness made in 1877 resurvey
of this township. Cedar live and standing with good upper face.
SW Hemlock stump in place, also.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 11/21/61
REGISTERED LAND SURVEYOR