

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 30 N. 6. W.	G-6; G-7
2. PROPERTY CONTROLLING IN SECTION	15, T. 30 N. 6. W.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 29, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-6 Found Ir. lying down in east edge of old, narrow horse & buggy days road grade. Fits Hebden's 1877 re-survey of N 1/2 of T30N-R6W.
- G-7 Restored S.W. Cor. of Sec. 15; equidistant between 1/4 Corners to N & S - equals Hebden pro-rated to N. & G.L.O. pro-rated to S. - and at record Hebden (1877) deflection SW at 1/4 Cor. to N. This fits Hebden's tie to stream to east, 440'+ (Hebden dropped a chain) & also fits Hebden's tie to stream (1840'+) to N.
- 15 Set 1/8 Cor. per Standard B.L.M. Instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6	G-7	15
Set DNR Mon. & Ced. Post on E. Side of old N-S trail rd. grade.	Set DNR Mon. & Ced. Post.	Drove 5/8"X40" re-rod w/RLS cap & Ced. Post w/Loc. Tag.
14" Maple S39°W 23.0	10" Maple S17°W 18.6	6" Maple N34°E 18.9'
10" Maple N42°W 15.1	17" Y. Birch S47°W 34.64	16" Maple S11°E 25.1'
12" Maple N35°E 26.7	23" Beech N06°E 29.44	7" Maple N28°W 36.2'
Ctr. Old N-S trail Due W 2'+	16" Maple N72°E 43.0	E-W Random Due N 3.5'+
N-S Random Due W 3.0	Old N-S trail road grade Due E 12'+	
	8" Maple S50°E 56.8	

SIGNED BY Carl F. Roser 6-6-79 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CHESTONIA TOWNSHIP
ANTRIM COUNTY