

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 30 N. R. 6 W.	G-5; H-5; I-5
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 5, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- G-5 Restored NW Cor. Sec. 15 double across 1/4 Cor. & Sec. Cor. to E. per B.L. Caukins, Co. Surveyor, survey of this Sec. Line, May 1925. (He retraced Hedden's 1877 Re-survey.)
 - H-5 Restored 1/4 Cor. Comm. to Sec's. 10&15 from two dead elm Wit. trees, still standing, B.L. Caukins, Co. Surveyor, 1925; 20" Elm (10"), S25 1/2 W, 12.2'; 16" Elm (8"), S63°E, 44.5'.
 - I-5 Found & accepted old squared Ced. post w/notches on 4 corners. Corner fits survey of N. Line Sec. 15 by B.L. Caukins, County Surveyor, dated May 1925; notes in large brown Co. Sur. Record No. 1, Pg. 387; Antrim Co. Reg. Deeds.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5	H-5	I-5
Set DNR Mon. & Ced. Post.	Set Std. DNR (short) Mon., buried 0.5 ft.	Fd. 4" sq.X5 1/2' pointed Ced. post w/Notches replaced w/DNR Mon. & Ced. Post & re-set old Post as evidence.
5" Maple N09°W 55.1'	22" Maple N28°W 73.20	4" Maple S28°W 26.7
6" Maple N70°E 29.4'	20" Maple S60°W 52.92	4" Maple S68°W 35.4
5" Maple S66°E 30.5'		3" Ironwood N46°W 55.4
Ctr. Trail to N. Due W 29'+	Ctr E-W gravel Rd. to E. Due N. 3'+	
Ctr. Trail to E. Due S 25'+	Ctr. N-S gravel Rd. to N. Due W. 7'+	
	Set Ced. Post w/Loc. Tag S45°E 30'	

SIGNED BY Carl F. Roser 6-6-79 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CHESTONIA TOWNSHIP ANTRIM COUNTY