

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 30 N. R. 6 W.	E-7; F-7
2. PROPERTY CONTROLLING IN SECTION 16	T. 30 N. R. 6 W.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 8, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 E-7 Accepted 2" pipe as found & accepted by R.L.S., N.B. DeYoung in 1977 Survey.

F-7 1/4 Cor. estab. equidistant and on line between Fd, Sec. Cor. to W. and estab. Sec. Cor. to E, equals single proportion to Hebden's 1877 re-survey.

15 Set 1/8 Cor. per Standard B.L.M. Instructions. Old Corner fence post position (found hole-post gone-- fence remains N & W) is N46°E 42.5'+.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

		F-7	15
Fd. 2" Pipe & set Ced. post w/Loc. Tag.		Set DNR Mon. & Ced. post	Drove 5/8"X40" re-rod w/Plastic Cap & set Ced. post w/Loc. Tag.
4" Maple S80°W 1.95		5" Ironwood S04°W 16.1	14" Maple S45°E 5.0
9" Maple N11°E 14.50		6" Maple S65°W 18.5	12" Maple S43°W 21.1
23" Maple S80°E 36.57		8" Maple N70°W 12.5	4" Maple N49°E 17.9
8" Maple S06°W 23.70			
Ctr. E-W Trail Rd.			Ctr. E-W buggy trail
Due N 16'+			Due N, 22'+
Fd. 3/8" Re-rod w/ RLS Cap			
Due N 33.00			


SIGNED BY Carl F. Roser 6-6-79 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CHESTONIA TOWNSHIP
 ANTRIM COUNTY