

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 30 N. R. 6 W.	G-3; G-4
2. PROPERTY CONTROLLING IN SECTION.....	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. S. R. E. W.	
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 9, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-3 Established NE Cor. Sec. 9; pro-rated to Hebden's 1877 re-survey for direction and distance, between the NW corner of Sec. 15 (this survey) and the corner to Sec.'s 3 & 4 on third correction line (previous Dept. Survey - June 1962-K. Ostling).
- G-4 Set DNR Mon. for E 1/4 Cor. Sec. 9; pro-rated to Hebden's 1877 re-survey for direction and distance, between the NW Corner of Sec. 15 (this survey) and the corner to Sec.'s 3 & 4 on third correction line (previous Dept. Survey - June 1962 - K. Ostling).


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3	G-4
Set DNR Mon. & Ced. Post	Set DNR Mon. & Ced. Post
8" Maple N04°W 25.5'	5" Maple N65°W 11.2'
7" Maple N54°E 21.4'	6" Maple N48°E 40.1'
7" Maple S50°E 47.7'	10" Maple S58°E 44.5'
6" Maple S70°W 23.5'	N-S hiking Trail
Ctr. N-S Trail Rd. Due E 4'	Due W 29'

SIGNED BY Carl F. Roser 6-6-79 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES.



SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_  
CHESTONIA TOWNSHIP  
ANTRIM COUNTY