

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
PUBLIC LAND SURVEY	T. 30 N. R. 7 W.	G-1; H-1
PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
LOT NO. _____, RECORDED PLAT _____		
PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 27, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a decree of a Court of law:

Description of original monument and accessories and/or subsequent restoration:

Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Restored the NW corner of Sec. 3, T30N, R7W, on third correction line, on line across the SW corner of Sec. 3 & very definite creek junction S of the NW corner of Sec. 3. This creek or stream jct. is noted in both the 1855 US line notes & in F.S.Church's survey of Sec. 3, dated 1909 & 1911. The NW corner of Sec. 3 was restored at record distance N of creek jct. of 618' per Church survey. The S $\frac{1}{4}$  corner of Sec. 34, T31N, R7W, is S87°55'E, 244.20'.  
 Reestablished N $\frac{1}{4}$  corner Sec. 3, T30N, R7W on third correction line equidistant & on line between NE & NW corners on Sec. 3 per F.S.Church survey of Sec. 3 of record, dated 1909 & 1911. The section corner common to Sec. 34 & 35, T31N-R7W is S87°55'E, 222.73'.  
 Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1

- Set DNR mon. & cedar post
- 9" Maple S65°W 19.9
- 12" Twn.B.Cherry S25°W 39.7
- 5" Ironwood S13°E 10.4
- 10" Twn.B.Cherry N75°E 26.0
- Random South Due W 17'±

H-1

- Set DNR mon. & cedar post
- 7" B. Cherry N87°W 49.0
- 5" Cedar S61°W 61.8
- 10" Y. Birch S04°W 35.6
- 4" Ironwood N04°E 30.7
- Old E-W fn. remains Due N 5'
- E-W Random Due N 0.5


SIGNED BY Carl F. Roser 9-15-76 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

KEARNEY TOWNSHIP  
ANTRIM COUNTY