

FEB 17 1994

ANTRIM COUNTY MICHIGAN RECEIVED FOR RECORD

93 DEC 13 AM 9:32

002 173

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Wanda R. Conway REGISTER OF DEEDS

For corners in

ANTRIM

(County)

Located in: Corner Code #

- 1. Public Land Survey T 30N R 7W A-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

I, NEIL L. WAY, in a field survey on DEC 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Cell (7, A) contains a black dot.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7 NW COR SEC 19

GLO SET COR

- SUGAR 20 S14W 35L
SUGAR 12 N21W 51L
LYNN 9 S21E 25L
SUGAR 14 N59E 19L

F. CHURCH, CO SURVEYOR USED COR AND TESTED IT MAY 2, 1893, PG 196 OF CO RECORDS. HE DID NOT WITNESS IT. HE ALSO USED IT OCT 29, 1913, HE DID NOT WITNESS IT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 NW COR SEC 19

FOUND 1/2" RE/ROD AND CAP #12026 IN MONUMENT BOX AS SET BY E. OSTLING FROM A PK NAIL HE FOUND SEPT 11, 1972 AND RECORDED ON LCR IN LIB 199 AT PAGE 233. COR IS 3' WEST OF CENTERLINE AND ON LINE WITH FNC WEST. ACCEPTED THIS AS TRUE SEC COR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 NW COR SEC 19

REPLACED 1/2" IRON ROD WITH ANTRIM COUNTY MONUMENT AND MONUMENT BOX.

- N34E 68.66' SPK SET 4' UP W SD P. POLE
S22E 112.4' SPK FD 3' UP W SD 10" CEDAR
WEST 36.61' SPK SET 2' UP N SD FNC POST
N67W 95.35' SPK SET 2' UP S SD 8" POPLAR
S60W 74.84' SPK SET 3' UP SE SD 8" POPLAR

Signed by NEIL L. WAY 28432 Surveyor's Michigan License No.

Date DEC 10, 1993

