

Dec 4 2 27 PM '96

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Wanda R. Conway*

For corners in

ANTRIM (County)	Located In:	Corner Code #
1. Public Land Survey	T 30N R 8W	A-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS  
  
SURVEY &  
REMONUMENTATION  
  
JUL 30 1996  
  
SECTION  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, NEIL L. WAY, in a field survey on 4, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SET POST AUG. 1855, BEECH 9 S64W 43, SUGAR 14 N9W 16, BEECH 9 N10E 32, BEECH 15 S53E 28  
CHURCH JUNE 1884 FOUND OLD STK & WIT'S  
CHURCH MAY 1892 FOUND CEDAR FENCE POST & WIT'S  
OSTLING FEB 1972 SET IRON & CAP AT CEDAR FENCE POST.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON & CAP OSTLING # 12026 AT OLD FENCE CORNER TO SOUTH & WEST & 1/2 CHAIN EAST OF CREEK AS NOTED IN GLO NOTES

Ratified by peer group  
in accordance with  
P.O. 345  
Antrim Co. Chairman  
*Arthur L. Lennox*  
Arthur L. Lennox  
Nov. 26, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET CO. MONT.  
N73E 25.30' MPL 10  
S45E 17.30' MPL 10  
N65W 10.42' MPL 12" TWIN  
S53W 8.93 MPL 10



Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 28432

Date NOVEMBER 22, 1996

LIBR 002 TAG 344