

SURVEYS
REMONUMENTATION

FEB 17 1994
LRLS 002
COMMISSION 171

ANTRIM COUNTY
MICHIGAN
RECEIVED FOR RECORD

93 DEC 13 AM 9:31

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Wanda R. Conway
REGISTER OF DEEDS

For corners in
ANTRIM

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey | T | 30N | R | 7W | C-7 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, NEIL L. WAY, in a field survey on DEC 10, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-7 NW COR SEC 20

GLO SET POST
CEDAR 18, N34E 34L
BIRCH 10, S34W 17L

NO EVIDENCE FOUND

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 NW COR SEC 20

FOUND 1 1/4" X 36" COUNTY IRON (CAP MISSING) @ CENTERLINE INTERSECTION ROADS NORTH SOUTH AND EAST, AND 1 1/2' NORTH OF FENCE LINE WEST IN BURIED MONUMENT BOX.
ACCEPTED THIS AS TRUE SEC CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 NW COR SEC 20

REPLACED 1 1/4" IRON PIPE WITH ANTRIM COUNTY MONUMENT AND MONUMENT BOX.

S20E 86.00' SPK FND 5' UP SW SD P. POLE
S38E 91.50' SPK FND 3' UP NE SD 10" J. PINE
N31E 81.85' SPK FND 2' UP W SD P. POLE
S86W 34.95' NE COR CHAIN LINK FENCE



Signed by Neil L. Way
Surveyor's Michigan License No. 28432

Date DEC 10, 1993