

**SURVEY
REMONUMENTATION**

ANTRIM COUNTY
MICHIGAN
RECEIVED FOR RECORD

93 DEC 13 AM 9: 32

FEB 17 1994

REF 002 Tab 172

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Wanda R. Conway
REGISTER OF DEEDS

For corners in
ANTRIM
(County)

Located In: _____ Corner Code # _____

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>30N</u> R <u>7W</u> | <u>D-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7		●										
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, NEIL L. WAY in a field survey on DEC 10, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-7 N 1/4 COR SEC 20

GLO SET 1/4 POST 1855
W.PINE 30 N20E 19L
CEDAR 12 S50E 21L

NO EVIDENCE FOUND

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7 N 1/4 COR SEC 20

FOUND 5/8" IRON ROD IN MONUMENT BOX IN CENTERLINE EAST WEST ROAD @ MID POINT ON LINE WITH SEC COR'S TO EAST AND WEST.
ACCEPTED THIS AS TRUE 1/4 CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7 N 1/4 COR SEC 20

REPLACED 5/8" IRON WITH ANTRIM COUNTY MONUMENT AND MONUMENT BOX.

S32W 42.90' SPK FND 5' UP NW SD 6" CEDAR
S43W 52.32' SPK FND 5' UP NW SD 6" CEDAR
N30W 83.20' SPK SET 4' UP SW SD 3" FIR
N74E 115.97' SPK SET 4' UP SE SD P.POLE



Signed by *Neil L. Way* Date DEC 10, 1993
Surveyor's Michigan License No. 28432