

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ANTRIM COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 NOV 30 3 55 PM '94
 REGISTER OF DEEDS
Walter R. Cross

For corners in

ANTRIM
 (County)

Located In: sec 21 Corner Code #

- | | | | | |
|------------------------------------|---|-------------|------------|------------|
| 1. Public Land Survey | T | <u>30</u> N | <u>7</u> W | <u>E-9</u> |
| | T | _____ | _____ | _____ |
| | T | _____ | _____ | _____ |
| | T | _____ | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | _____ | _____ |
| | S | _____ | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | _____ | _____ |
| | S | _____ | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____ SECTION _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, NEIL L. WAY, in a field survey on OCT 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-9
 GLO SET CORNER POST OCT 1855
 CEDAR 9 N40W 19
 CEDAR 16 S67E 43

NO EVIDENCE FOUND

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9
 FOUND 1" IRON PIPE AND TWO OLD CEDAR STAKES.

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *Arthur L. Lennox*
 Arthur L. Lennox
 Date: Oct. 6, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9
 SET COUNTY MONUMENT
 S75E 11.22' BALSM 4"
 N17E 15.95' CEDAR 6"
 N39W 14.64' CEDAR 10"
 N77W 15.20' CEDAR 12"
 S17W 29.30' HEMLOCK 10"
 S03E 5.70' 1/2" IRON #20703 BOSS



Signed by NEIL L. WAY *Neil L. Way* Date NOV 21, 1994

Surveyor's Michigan License No. 28432