

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ANTRIM

(County)

Located In: SEC 21 Corner Code #

- | | | |
|------------------------------------|--------------------------|-----------------|
| 1. Public Land Survey | T <u>30N</u> R <u>7W</u> | <u>F-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <u>SURVEY 8</u> |
| | S _____ T _____ R _____ | <u>RECORDED</u> |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

ANTRIM COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 NOV 30 3 54 PM 1994
 REGISTER OF DEEDS
 L. D. R. COMPANY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, NEIL L. WAY, in a field survey on OCT 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-9
 GLO SET CORNER OCT 1855
 BLK ASH 10 N30E 37
 CEDAR 24 S38W 28

NO EVIDENCE FOUND

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9
 FOUND 3/4" IRON PIPE

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *[Signature]*
 Arthur L. Lennox
 Date: Oct. 6, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9
 SET COUNTY MONUMENT
 N75W 127.42' CEDAR 16"
 S50W 29.58' P. POLE
 N55W 62.90' MPL CLUMP
 N25E 3.73' BALSAM 8"
 S25E 5.00' BALSAM 8"



Signed by NEIL L. WAY *[Signature]* Date NOV 21, 1994

Surveyor's Michigan License No. 28432

002 207