

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ANTRIM
(County)

Located In: SEC 22 Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------------------------------|
| 1. Public Land Survey | T <u>30N</u> R <u>7W</u> | <u>I-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <u>SURVEY & REMONUMENTATION</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

ANTRIM COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 NOV 30 3 48 PM '94
 Wanda R. Combs
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____ SECTION _____

I, NEIL L. WAY, in a field survey on OCT 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-8
 GLO SET CORNER POST OCT 1855

 Y-BIRCH 6
 HEMLOCK 28

NO EVIDENCE FOUND

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8
 FOUND 3/4" IRON PIPE AND CAP #3920

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman *Arthur L. Lennox*
 Arthur L. Lennox
 Date: Oct. 6, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8
 SET COUNTY MONUMENT

 N05E 34.05' MPL 10"
 N45W 67.53' POP 8"
 S04W 36.76' CHY 4"
 S54E 52.76' CHY 10"



Signed by NEIL L. WAY *Neil L. Way* Date NOV 21, 1994
 Surveyor's Michigan License No. 28432