

SURVEY & LAND CORNER RECORDATION CERTIFICATE
REMONUMENTATION

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

APR 26 1995

FOR COMMISSION	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>27</u> T. <u>30</u> N. S., R. <u>7</u> E. W.		<u>I-10</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. S., R. _____, E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. S., R. _____, E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

ANTRIM COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 DEC 5 1 59 PM '94
 REGISTER OF DEEDS
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Terry B. Smith, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on DEC 12, 1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on DEC 12, 1994, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

GLO Corner Post Oct. 1855 LCRC recorded Liber 001 page 243
 Lynn 14 N22W 14 June 1978 LS#20357
 Sugar 18 S62E 32
 No. evidence found

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

found 1 1/2" iron pipe & witnesses

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 -- E 1/4 Corne Sec. 27, T30N, R7W
 Peer group approval Oct. 6, 1994
 Set Antrim County Monument
 12" Basswood S72°E 11.8
 12" Maple S10°W 14.40
 10" Maple North 25.00
 16" Ash N20°W 27.30

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman Arthur L. Lennox
 Date: Oct. 6, 1994


SIGNED BY Terry B. Smith DATE NOV. 30, 1994

SURVEYOR'S MICHIGAN REGISTRATION NO. 25873

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



222 223

SURVEYOR'S MICHIGAN REGISTRATION NO. _____