

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


ANTRIM COUNTY
T 31 N R 5 W

DESCRIPTION OF CORNER W 1/4 corner, Section 5

CORNER MONUMENT Set DNR Monument

DATE MONUMENT PLACED AND WITNESSED 11-19-71

WITNESSES TO CORNER..... 6" Maple S 73 W 21.6'



9" Maple S 51 E 27.9'

6" Maple N 29 W 34.5'

AND N-S Fm. remains Due E 13.5'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner reestablished per standard BLM instructions. a 1/2" rod, set in last few years, is in old N-S fence remains and is 48' N and 15" E of 1/4 corner; this rod apparently having been set on the split of the mile which does not take into consideration the U.S. meander ~~XXXXXX~~ and run-out of the N. Twp. line. Also see Restoration Procedure B for Corner Code C-1, NW corner of Sec. 5 (31-5).



SURVEYOR'S SEAL

SIGNED Carl F. Roser DATE 11-26-71
REGISTERED LAND SURVEYOR 12028

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68