


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

ANTRIM COUNTY
T 31 N R 5 W

DESCRIPTION OF CORNER NE corner of Section 2
CORNER MONUMENT Set DNR monument
DATE MONUMENT PLACED AND WITNESSED 10-15-71
WITNESSES TO CORNER..... 4" Maple N 6 E 7.0'



7" Maple tw. N 82 W 29.6'
7" Maple twin S 61 E 50.4'
AND
E-W Trail road Due S 95'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner reestablished at double the distance of a line projected through the N 1/4 corner of Sec. 2 and the E 1/16 corner on the N line of Section 2, this being an old E-W fence remains with old fence corner at E 1/16.

A 1/16 corner positioned by this method fits the U.S. tie South to stream crossing within less than 10' (630'-Mea.). Occupancy (old fence) was accepted on the N line of the NE 1/4 of Sec 2, since there is a record of survey activity along this line, dated 1894 and 1885; see old County Surveyor's Book S & C-302 at Charlevoix County Register of Deeds.



SIGNED Carl F. Roeser DATE 10-22-71
REGISTERED LAND SURVEYOR 12028

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68