

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 31 N.R. 5 W.
T. 31 N.R. 6 W.


Antrim COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 30 - 31 - 25 - 36

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 29, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

8" H. Maple S 35 W 31.6'

9" H. Maple N 68 E 12.2'

AND 8" Elm N 80 W 27.4'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by proportionate measurement between corners 1 mile north and town corner south while making a survey in this area.

Unable to identify anything for U. S. evidence, but this fits calls of U. S. record very well. Falls on east edge of old N - S trail.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE July 10, 1962
REGISTERED LAND SURVEYOR