MICHIGAN DEPARTMENT OF CONSERVATION FORESTRY DIVISION

LAND CORNER RECORD

		T.	31	N.R.	5 W. 6 W.		
		1.	יוכ	14 6 14 0		Antrim	COUNTY
E30	RIPTION OF CORN	IER Town corne	r common	to Sect	lon 31, T31NR5	and Section	n 36, T31NR66
ORI	IER MONUMENTS	Set 1" pipe wit	h 4" bra	ss cap			
ATE	MONUMENT PLACE	D AND WITNESSED_	June	28, 196	2		
i Ti	ESSES TO CORNER						
N [
N	į		<u>5#]</u>	faple	N 75 W	14.01	
4	<i>9</i> 6'	· -	8# I	il m	S 75 E	32.61	
		AMD	۴				

DESCRIPTION IN DETAIL AS TO NOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored while making a survey of the Third Correction Line. Set corner 25 links east of the north 1/4 corner of Section 1. T30NR6W as prescribed by a survey of record by Robinson in 1909 which identified both the Hebdon 1/4 corner and this town corner. Unable to identify anything for evidence of the previous surveys —but conclude this method to be most in agreement with the conditions existing in 1909. Checks very well for measurement and bearing north and west.

See map and minutes of survey for further information.

SURVEYOR'S SEAL

SIGNED Leweth Lotting DATE July 10, 1962

REGISTERED LAND SURVEYOR