

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES


LAND CORNER RECORD

ANTRIM COUNTY
T 31 N R 5 W

DESCRIPTION OF CORNER NW corner, Section 5
CORNER MONUMENT Set DNR Monument
DATE MONUMENT PLACED AND WITNESSED 11-19-71

WITNESSES TO CORNER.....

<u>12" Maple</u>	<u>N 79 W</u>	<u>32.2'</u>
<u>9" Maple</u>	<u>N 9 E</u>	<u>26.7'</u>
<u>14" Maple</u>	<u>S 13 E</u>	<u>36.4'</u>
<u>N-S Fence Remains</u>	<u>Due E</u>	<u>18'</u>
AND		
<u>Old Overgrown N-S Rd. Grade</u>	<u>Due W.</u>	<u>12'</u>
<u>E-W Random</u>	<u>Due S</u>	<u>12.7'</u>



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner reestablished about one rod West of, and parallel to, old fence remains South, and on straight line between section corners 1/2 mile West and two miles East, which is very close to a corner by proportionate measure E and W. The Southerly end of the fence South appears to be a ROW fence near East side of County Road about a 1/4 mile North of SW corner of Sec. 5. The old road grade some 12 ft. West of the NW corner of Section 5 was built prior to 1887 and was probably not built on the N-S Sec. line, according to Henry Korthase.

SURVEYOR'S SEAL

SIGNED Carl F. Rorer DATE 11-26-71
REGISTERED LAND SURVEYOR 12028

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68