

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 31 N.R. 6 W.


Antrim COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 33 - 34 on south boundary of township

CORNER MONUMENT Set 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED June 28, 1962

WITNESSES TO CORNER..... 10" H. Maple N 5 E 27.2'



6" H. Maple N 86 W 16.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey of the Third Correction line in this township. Found 2 foot of small gauge RR rail at corner as established in very old previous survey by unknown surveyor. Unable to definitely conclude this to be an original corner, but appears to have been in existence for considerable time and was used in other surveys in this area. Checks for bearing and measurement to other corners, and must be considered the best available evidence of proper location for corner. Appears to be the only corner available for control of the correction line through this township.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE July 10, 1962