

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>31</u> N. <input checked="" type="radio"/> R. <u>6</u> W. <input checked="" type="radio"/>	<u>E-12; E-13</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION <u>32</u>	T. <u>31</u> N. <input checked="" type="radio"/> R. <u>6</u> W. <input checked="" type="radio"/>	<u>XX = on line & equidistant between C-12 & 10, Sec.32</u>
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 7, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on November 7, 1974, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-12 Found 2"x24" galv. pipe w/bolt in top in place. Added DNR mon. No history of corner, except it appears to have been used as basis of staking small parcels in W $\frac{1}{2}$ SW $\frac{1}{4}$ Sec. 33.
- E-13 Corner on third correction line common to Sec's 32 & 33 T31N-R6W, was recovered and accepted in previous dept. survey, dated 1962 (1" axle shaft). The N $\frac{1}{4}$ corner of Sec. 5 T30N-R6W is S89°48'30"E, 323.22'.
- XX Established SW corner of N $\frac{1}{2}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ of Sec. 32 at S00°05'20"E, 653.4' from W $\frac{1}{2}$ Sec. 32.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12	E-13	XX
Set DNR mon. & cedar post	Fd. 1" iron (axle shaft) & set cedar post	Set 1 $\frac{1}{4}$ "x36" pipe & cedar post w/loc. tag
5" Balsam N23°W 36.40	12" B. Cherry S14°W 55.7	10" Cedar N20°E 32.7
5" Spruce N88°E 14.24	8" Maple N02°W 26.3	6" Cedar N56°E 20.4
5" Spruce S27°W 33.43	10" B. Cherry N71°E 36.2	9" Cedar N52°W 44.4
N-S Random Due W 3'	on Random E-W-N	N-S Random Due E 3.8

SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ JORDAN TOWNSHIP ANTRIM COUNTY

