

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>31</u> N. <u>6</u> R. <u>6</u> W.	<u>C-10; C-12; D-13</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, Carl R. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 7, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-10 Found & accepted 1"x48" pipe in place; corner falls near SW corner of old field.
- C-12 Reestablished ¼ corner equidistant & on line between section corners to N & S.
- D-13 Reestablished ¼ corner on third correction line, equidistant & on line between SE & SW of Sec. 32. The corner common to Sec's 5 & 6 T30N-R6W is S89°23'E, 340.94'. At 42'± E and 4'± S of our reestablished S¼ of Sec. 32 there is an old cedar post (stdg.) w/one post to N & W (down). This would fit tie as shown on 1935 MSHD M-66 plans. Hwy. plans indicate tie only & do not describe the corner; we did not accept this post for corner as it does not fit recovered section corner ½ mile to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10	C-12	D-13
Fd. pipe & added DNR monument & cedar post	Set DNR mon. & cedar post	Set DNR mon. & cedar post
8" Maple S77°E 11.3	5" Cedar N88°W 35.3	4" W. Pine N25°E 19.0
5" Cedar S38°W 39.2	6" Cedar S52°E 57.6	8" Hemlock N60°E 68.8
8" Maple S71°W 44.4	3" Cedar N42°E 46.9	16" W. Pine S19°E 59.9
6" Maple N55°W 50.4	Power Pole N43°W 143.88	14" W. Pine S86°W 72.9
	Ctr. Line Power Line	E-W random Due S 28'
	Due N 100±	
	N-S random Due E 5.1	


SIGNED BY Carl F. Roser 9-15-76 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ JORDAN TOWNSHIP ANTRIM COUNTY