

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>31</u> N. <u>6</u> W. <u>●</u>	C-9; D-9
2. PROPERTY CONTROLLING IN SECTION <u>29</u>	T. <u>31</u> N. <u>6</u> W. <u>●</u>	2
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 2, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 1-9 Found buggy nut & stones 1966. Since that time M. Feindt RL.S. has used this corner and set ½" black pipe. We added a standard DNR mon. in 1975. Corner fits M.D.S.H. M-66 plan data, dated 1935.
- 1-9 Restored ¼ corner per R.L.S. M. Feindt survey in Sec. 20, dated 1963 and per her survey of part of the SE¼ SW¼ of Sec. 20 for L. Mitchell, dated March, 1968.
- 2 Established 1/16 corner equidistant and on line between ¼ corner W & section corner E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9	D-9	2
Set DNR monument	Drove 1¼" x 36" pipe	Drove 1-1/8"x18" iron rod in
Power Pole N73°E 131.3	20" W. Pine S13°W 97.71	blacktop
Power Pole S63°W 69.4	22" W. Pine N15°E 64.92	16" W. Pine S30°W 70.59
Set cedar post w/loc. tag	25" Spruce N47°W 85.19	16" W. Pine S50°E 104.35
Due N 33'	Center E-W b'top Co. Rd.	6" W. Pine N14°E 55.10
Fence Corner Due N 30'	Due N 12'	Center E-W b'top Co.Rd. Due N 6.0
Co.Rd. b'top in curve	Set cedar post w/loc. tag	Set cedar post w/loc. tag
Due S 28'	Due S 21'	Due S 33'


SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ JORDAN TOWNSHIP
ANTRIM COUNTY