

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>31</u> ^{N.} <input checked="" type="radio"/> , R. <u>7</u> ^{W.} <input checked="" type="radio"/>	<u>J-13</u>
2. PROPERTY CONTROLLING IN SECTION <u>35</u>	T. <u>31</u> ^{N.} <input checked="" type="radio"/> , R. <u>7</u> ^{W.} <input checked="" type="radio"/>	<u>1; 8</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} <input type="radio"/> , R. _____ ^{E.} <input type="radio"/>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 28, 1975, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-13** Restored $S\frac{1}{4}$ corner Sec. 35, T31N-R7W on third correction line between the NE corner of Sec. 3, T30N-R7W & the SE corner of Sec. 35 T31N-R7W per F.Church survey of Sec. 35 of record, 1887 & 1888. The departure (longitude) of $S\frac{1}{4}$ Sec. 35 was established on line across recovered ctr. of Sec. 35 (Church's stake) & probably Church's stake for $S\frac{1}{4}$ but too far N by 9.3'. The NE corner of Sec. 3 T30N-R7W (fd. Church stk & wit.) is $N87^{\circ}40'W$ 201.27'.
- 1 Restored W 1/8 on N line of Sec. 35 equidistant & on line between recovered Church corners $\frac{1}{4}$ mile to E ~~W~~.
- 8 Recovered Church's 4" sq. ced. stake for W 1/8 on E-W $\frac{1}{4}$ line. Fits survey of 1887 & 1888.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13	1	8
Set DNR mon. & cedar post	Set 1"x36" pipe & cedar post	Set 1"x72" pipe & cedar post
6" Cedar $S85^{\circ}E$ 9.9	w/loc. tag	w/loc. tag
14" Tamarack $S20^{\circ}E$ 43.7	8" Twn. Maple $N38^{\circ}W$ 13.2	5" Twn. Cedar $S26^{\circ}E$ 21.4
6" Tamarack $N85^{\circ}W$ 13.7	10" Maple $S18^{\circ}E$ 22.2	9" Cedar $N54^{\circ}E$ 92.0
7" Tamarack $N33^{\circ}W$ 27.5	10" B. Cherry $S73^{\circ}E$ 37.2	5" Balsam $S76^{\circ}W$ 28.8
Old N-S swp. rd. Due W 7'±	E-W Random Due S 1.7'±	
Rand. Int. E-W-N $N03^{\circ}50'E$ 122.8		


SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____
 ECHO TOWNSHIP
 ANTRIM COUNTY