

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>31</u> N. <u>●</u> R. <u>7</u> W. <u>●</u>		<u>I-12; J-12; K-12</u>
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		_____
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on _____, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-12 Restored W $\frac{1}{4}$ corner, Sec. 35, T31N-R7W at double distance & on line across recovered center of sec. & W 1/8 on E-W $\frac{1}{4}$ line, per F.S.Church survey of Sec. 35, dated 1887 & 1888. Corner fits Church tie of 277' E to stream 12 links, course N. Corner is in line with center of sand trail to west.
- J-12 Recovered Church 3" sq. cedar stake for ctr. of Sec. 35. Fits Church survey dated 1887 by order of prosecuting attorney.
- K-12 Restored corner per Church survey of record, Sec. 35, 1887 & 1888; Church notes in large Vol. 1 of co. survey records, pp. 17-22 & 70-71 at Antrim Co. Reg. of Deeds.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12	J-12	K-12
Set DNR mon. & cedar post	Set 1 $\frac{1}{2}$ "x72" pipe & cedar	Set std. DNR mon. & ced. post
P. Pole S59 ^o W 60.48	post w/loc. tag	8" Cedar S85 ^o E 2.8
14" B. Cherry N69 ^o W 82.5	8" Twn. Cedar N14 ^o E 106.5	4" Cedar S30 ^o W 23.4
9" B. Cherry N19 ^o W 78.3	8" B. Cherry N41 ^o E 44.6	5" Cedar N85 ^o W 22.2
6" R. Pine S28 ^o E 88.40	7" B. Cherry N28 ^o W 16.0	N-S Random Due E 9.8
	18" W. Pine stp. S35 ^o W 36.0	Present E-W swamp edge
	Ctr. of old N-S corduroy	Due N 1 chain±
	logging road Due W 3'±	

SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ ECHO TOWNSHIP
ANTRIM COUNTY