

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>31</u> N. R. <u>7</u> W.	<u>I-13; M-11; M-12</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 11, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-13 Reestablished sec. corner common to Sec. 34 & 35, T31N-R7W, on third correction line, on line between the NE & NW corners of Sec. 3, T30N-R7W & equidistant between the S $\frac{1}{4}$ corners of Sec. 34 & 35 T31N-R7W. The N $\frac{1}{4}$ corner of Sec. 3 T30N-R7W is N87°55'W222.73'. There is an old haphazard fence intersection N77°E 50'±.
- M-11 Restored sec. corner in N-S wheel track on average of split of old twp. rd. grade R.O.W. fences to N & in line with old fence remains to E & W. This fits fence W at 1319'±N & 1"x4" stake & possible irreg. fence remains to E at 2638'± N.
- M-12 Reestablished $\frac{1}{4}$ corner equidistant & on line between section corners to N & S. Corner fits U.S. tie of 5 chains N to "Leave Swp." (to nearest chain) very good.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13	M-11	M-12
Set DNR mon. & cedar post	Set DNR mon. (buried)	Set DNR mon. & cedar post
10" Twn. B. Cherry S50°E 9.9	24" Apple N66°E 23.69	12" Cedar S70°E 42.5
10" Maple S04°E 11.0	20" Apple S45°E 67.22	N-S Random Due E 69.2
Tri. 2'x2'x1 $\frac{1}{2}$ ' rock	10" Tri-Maple N87°W 60.86	Power Pole N04°W 49'±2'
N62°W 20.5	Set cedar post w/loc. tag	
12" B. Cherry N36°W 36.5	Due W 33'	
10" Y. Birch N55°E 49.2		
E-W Random Due N 0.5		

SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

ECHO TOWNSHIP
ANTRIM COUNTY

