

LAND CORNER RECORDATION CERTIFICATE ANTRIM COUNTY MI.
Filing Requirement of Act 74, Mich. P.A. 1970 Register of Deeds

For corners in CENTRAL LAKE
ANTRIM Located In: Corner Code #
(County)

Recorded
12-22-1997 10:12:05

Wanda R. Conway
REGISTER OF DEEDS

1. Public Land Survey E 1/4 T. 31N R. 8W M-6
SEC 13 T. 31N R. 7W A-6
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
- SURVEY &
REMONUMENTATION

Register of Deeds Stamp & File Number

NOV 30 1997

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____ SECTION _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RICHARD J. KRAL, in a field survey on 8-21-97, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-6, 1/4 CORNER COMMON TO SEC. 13, T31N-R8W & A-6, SEC. 18, T31N-R7W
1856, RESURVEY TWP. BOUNDARY BY E.D. ATWATER; SET CORNER, 24" BEECH, N56°E, 24 LKS. (15.84'); 5" BEECH, S50 1/2°W, 11LKS (7.28')
1906, SURVEY BK. #1, PG. 256, BY B.L. CAUKIN DEPT. CO. SURVEYOR; SET BURIED OLD GLASS AND CROCKERY AT SINGLE PROPORTION MEAS.; NO ACCESSORIES.
1907, RESURVEY BK. 1, PG. 268, BY F.S. CHURCH CO. SURVEYOR, FD A BROKEN STEEL PLOW BEAN ON END WITH STONEWARE AND BOTTLES AROUND IT.
1909, SURVEY BK #1, PG. 300, BY F.S. CHURCH CO. SURVEYOR, NO DESCRIPTION OR ACCESSORIES, ONLY NOTE TO SEE PG. 268.
1973, SURVEY RECORDED IN LIB. 204, PG. 303 AND LCRC. RECORDED IN LIB. 204, PG. 301, BY P.E. CHENARD FD STEEL PLOW BEAM, 2' N. OF RD CENTERLINE 13" C. ELM, S53°E, 71.64'; 15" C. ELM, S45°E, 70.47'; 4" SQ. CONCRETE MON. S48°W, 46.42'
1993, SURVEY REC. IN LIB. 394, PG. 640; BY B.M. JONES, FD 1" IRON, P. POLE, N35°W, 47.80'; FEN. POST, S37°W, 42.20'; 28" MAPLE, S59°E, 84.43' 18" APPLE, N66°E, 72.40

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-6, 1/4 CORNER COMMON TO SEC. 13, T31N-R8W & A-6, SEC. 18, T31N-R7W
FD. 1 1/2" X 2 1/2" IRON PLOW BEAM IN CENTERLINE E-W ASPH. ROAD & 11' W. OF GR. ROAD N-S
PULLED & REPLACED WITH ANTRIM COUNTY MONUMENT (BERNTSEN MODEL G-1 [30" PISTON] WITH G-2 CAP).
FD. NAIL ON SIDE POWER POLE, N40°W, 47.70' (R. 47.80)
FD. NAIL ON SIDE CLUMP OF 5-5" APPLE, N61°E, 72.40' (R. 72.40')
FD. NAIL IN FACE PHONE POLE, S45°W, 42.22 (R. 42.20')
FD. BROKEN & BENT SQ. CONC. MON. (STRAIGHTENED SAME), S52°W, 46.31' (R. 46.42')
NO G.L.O. WITNESS WERE FOUND.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-6, 1/4 CORNER COMMON TO SEC. 13, T31N-R8W & A-6, SEC. 18, T31N-R7W
FD. 1 1/2" X 2 1/2" IRON PLOW BEAM IN CENTERLINE E-W ASPH. ROAD & 11' W. OF GR. ROAD N-S
PULLED & REPLACED WITH ANTRIM COUNTY MONUMENT.
FD. NAIL ON SIDE POWER POLE, N40°W, 47.70' (R. 47.80)
FD. NAIL ON SIDE CLUMP OF 5-5" APPLE, N61°E, 72.40' (R. 72.40')
FD. NAIL IN FACE PHONE POLE, S45°W, 42.22 (R. 42.20')
FD. BROKEN & BENT SQ. CONC. MON. (STRAIGHTENED SAME), S52°W, 46.31' (R. 46.42')
SET NAIL IN SIDE 19" MAPLE, S54°E, 85.10'

Ratified by Peer
Group in accordance
with P.A. 345
Antrim Co. Chairman

Arthur L. Lennox

Arthur L. Lennox
Nov. 18, 1997
Date 12-14-97



Signed by Richard J. Kral
Surveyor's Michigan License No. 26460