

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Liber 000003 Page 0152

For corners in "ECHO TWP"

ANTRIM (County) Located In: Comer Code #

1. Public Land Survey T 31N R 7W C-5
 T R
 T R
 T R

2. Property Controlling in Section S T R
 S T R
 S T R

3. Miscellaneous Property in Sec. S T R
 S T R

ANTRIM COUNTY MI.
 Register of Deeds
 Recorded

12-21-2000 11:09:40

Wanda R. Conway
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, NEIL L. WAY, in a field survey on DEC. 18, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-5 NE CORNER SEC. 18

GLO SET CORNER POST 1857. A 3 1/2" HEMLOCK STAKE.
 BEECH 7 N 85 1/4 W 58L
 HEMLOCK 11 S 69 3/4 E 46 L
 NO OLD CORNER

CHURCH FOUND OLD WIT'S, MAY 5, 1909
 BEECH 9 N 62 1/2 E 29L
 HEMLOCK 11 S 11 1/2 W 34 1/2 L

SURVEY &
 REMONUMENTATION

JAN 23 2001

SECTION

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5 NE CORNER SEC. 18

FOUND 1/2" IRON BAR AND CAP #28417 AS SET BY ROBERT MITCHELL JUNE 28, 1999 BY FENCE EVIDENCE, STREAM CALLS AND RELATIONSHIP TO GOV'T DIST'S N,S,E, AND W AND RECORDED IN LCR, LIBER 3, PAGE 57.

N72E 23.62' HEMLOCK 4"
 N72W 8.66' MAPLE 12"
 S13E 20.62' MAPLE 8"
 WEST 16.50' STREAM
 SOUTH 56' STREAM
 S38E 26.16' BOAT SPIKE

ALSO FOUND A BOAT SPIKE (S38E 26.16') BY CHARLEVOIX ABSTRACT AND RECORDED IN LCR LIBER 3, PAGE 10 BY LENNOX.

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5 NE CORNER SEC. 18

ACCEPTED MITCHELL IRON AS CORNER, REMOVED IRON AND REPLACED WITH COUNTY MONUMENT.

N72E 23.62' HEMLOCK 4"
 N72W 8.66' MAPLE 12"
 S13E 20.62' MAPLE 8"
 WEST 16.50' CREEK CL
 SOUTH 56' CREEK CL
 S38E 26.16' BOAT SPIKE

Ratified by Peer Group
 In accordance with
 P.A. 345
 Antrim Co. Chairman

Arthur L. Lennox

Arthur L. Lennox, P.E., P.S.
 Nov. 28, 2000

Signed by *Neil L. Way*

Date Dec. 18, 2000

Surveyor's Michigan License No. 28432