

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Libers 00003 Page 0151

For corners in "ECHO TWP"

ANTRIM (County)	Located In:	Corner Code #
1. Public Land Survey	T 31N R 7W	C-6
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

ANTRIM COUNTY MI.  
Register of Deeds  
Recorded

12-21-2000 11:09:29

Wanda R. Conway  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, NEILL WAY, in a field survey on DEC. 18, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-6 EAST 1/4 CORNER SEC. 18  
GLU SET CORNER POST, A HEMLOCK STAKE 3"  
SUGAR 28 N81 1/4W 21L  
SUGAR 12 S79E 33L  
CHURCH, MAY 5, 1909, L 300, P 301, A STAKE, NO WITS OR DESCRIPTION.  
MARY FEINDT, MAY 27, 1976, L 226, P 630 FOUND A 3/4" IRON PIPE AT FENCE INTERSECTION.  
LENNOX, SEPT. 18, 1984, L 290, P 1095 FOUND A 3/4" IRON PIPE AT FENCE INTERSECTION.

**SURVEY &  
REMONUMENTATION**

**JAN 23 2001**

**SECTION**

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6 EAST 1/4 CORNER SEC. 18  
FOUND 3/4" IRON PIPE AT FENCE CORNER INTERSECTION TO EAST, WEST AND SOUTH.

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6 EAST 1/4 CORNER SEC. 18

ACCEPTED 3/4" IRON PIPE AS CORNER, REMOVED AND REPLACED WITH COUNTY MONUMENT.

N25E 17.54' MAPLE 16"  
N30W 25.67' MAPLE 6" TW  
S75E 23.96' MAPLE 12"  
SOUTH 15.44 MAPLE 14"

Ratified by Peer Group  
In accordance with  
P.A. 345  
Antrim Co. Chairman

*Arthur L. Lennox*  
Arthur L. Lennox, P.E., P.S.  
Nov. 28, 2000



igned by Neil L. Way

Date DEC. 18, 2000

urveyor's Michigan License No. \_\_\_\_\_