

LAND CORNER RECORDATION CERTIFICATE ANTRIM COUNTY MI.  
Filing Requirement of Act 74, Mich. P.A. 1970 Register of Deeds

For corners in

Antrim  
(County)

Located In:

Echo  
Corner Code #

- 1. Public Land Survey NW 15 T 31 N R 7 W G-5  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_
- 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

12-18-2000 16:23:25

Monda R. Conway  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Terry B. Smith, in a field survey on Dec. 7, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |   |    |   |   |    |   |    |   |    |   |    |   |
|----|----|---|----|---|---|----|---|----|---|----|---|----|---|
|    | A  | B | C  | D | E | F  | G | H  | I | J  | K | L  | M |
| 1  |    |   |    |   |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

1857 GLO Post used in correction line  
1906 B. L. Caulkin, County Surveyor -- division of Section 10  
1993 certificate by J. Ferguson



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

found 1 1/2" pipe per certificate by Ferguson  
measurement to other accepted corners checks with 1993 certificate  
Peer group -- property controlling corner

SURVEY &  
REMONUMENTATION

JAN 23 2001

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

found 1 1/2" pipe -- set antrim county monument inside pipe  
6" Maple S40W 37.80  
NE Corner cabin S45W 76.40  
NW Corner cabin S55W 95.80  
UP N65W 47.38

Ratified by Peer Group  
In accordance with  
P.A. 345  
Antrim Co. Chairman

Arthur L. Lennox, P.E., P.S.  
Nov. 28, 2000

Signed by Terry B. Smith  
Surveyor's Michigan License No. 25873

Date 12-18-2000