

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Antrim
(County)

Located In:

Echo

Corner Code #

- 1. Public Land Survey N $\frac{1}{4}$ 15 T 31NR 7W H-5
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___
- 3. Miscellaneous Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___

ANTRIM COUNTY MI-
Register of Deeds
Filed

12-18-2000 16:22:10

Manda R. Conway
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Terry B. Smith, in a field survey on Dec. 7, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1857 GLO set Hemlock post @ 40.06 chains
- Hemlock 24 N22 $\frac{1}{2}$ W 13 lks
- Hemlock 24 S60 $\frac{1}{2}$ E 16 lks
- 1993 certificate by J. Ferguson



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- found $\frac{1}{2}$ " steel bar in roadway per 1993 certificate
- measurements to east and west check with said 1993 certificate
- peer group -- long established locally property controlling corner

SURVEY &
REMONUMENTATION

JAN 28 2001

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- set antrim county monument beside steel bar
- Corner fence post N03E 34.00
- 12" Poplar South 25.68
- 10" Poplar S20W 35.54
- 11" Poplar S36E 40.04

Ratified by Peer Group
In accordance with
P.A. 345
Antrim Co. Chairman

Arthur L. Lennox, P.E., P.S.
Nov. 28, 2000

Signed by Terry B. Smith
Surveyor's Michigan License No. 25873

Date 12-18-2000