

**SURVEY &  
REMONUMENTATION**

**JAN 23 2001**

Liber **000003** Page **0133**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

ANTRIM COUNTY MI.  
Register of Deeds  
Filed

For corners in **SECTION**

Echo

<u>Antrim</u> (County)	Located In:	Corner Code #
1. Public Land Survey E $\frac{1}{2}$ 14	T <u>31N</u> R <u>7W</u>	<u>K-6</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

12-18-2000 16:22:56

Wanda R. Conway  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Terry B. Smith, in a field survey on December 19, 2000 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1857 Govt. 3" Beech post
- Sugar 22 S53W 41 lks
- Sugar 12 N16 $\frac{1}{2}$ E 49 lks
- 1905 B.L. Caulkin, County Surveyor
- 1973 LCRC by L. Gerschbacher Liber 204 pg. 27 set monument midway and on line

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

found concrete monument and witnesses per 1973 LCRC



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 12-07-00 set antrim county monument adjacent to concrete monument
- K-6 E $\frac{1}{2}$  Corner Section 14, T31N, R7W
- 14" Hemlock S70E 51.86
- 10" Beech S45W 24.06
- 30" Beech Stump N25W 14.14
- 10" Maple S20E 13.15
- 10" Yellow Birch S10W 26.12

Ratified by Peer Group  
In accordance with  
P.A. 345  
Antrim Co. Chairman

*Arthur L. Lennox*

Arthur L. Lennox, P.E., P.S.  
Nov. 28, 2000

Signed by *Terry B. Smith*  
Surveyor's Michigan License No. 25873

Date 12-18-2000