

JAN 23 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ANTRIM COUNTY MI.
Register of Deeds
Filed

For corners in

<u>Antrim</u> (County)	Located In:	Echo Corner Code #
1. Public Land Survey	SE 14, T31N R 7W	K-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

12-18-2000 15:22:42

Manda E. Conner
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Terry B. Smith, in a field survey on Dec. 07 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1857 GLO set Cedar Post
- Cedar 15 N67½E 10 lks
- B. Ash 12 S42½W 34 lks
- 1905 County Surveyor B. L. Caulkin
- 1972 Certificate L. Gerschbacher
- 1097 Certificate A. Lennox
- 1979 LCRC A. Lennox
- 1985 LCRC B. Jones
- 1972 LCRC L. Gerschbacher

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

found 1" Steel bar per recorded documents
Peer group corner is "locally accepted corner"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Ser Antrim County Monument over steel bar
- 8" Cedar S50E 31.90
- 8" leaning Cedar East 32.65
- 8" Forked Cedar S40W 54.42
- 5" Ash N70W 30.52



Ratified by Peer Group
In accordance with
P.A. 345
Antrim Co. Chairman

Arthur L. Lennox
Arthur L. Lennox, P.E., P.S.
Nov. 28, 2000

Signed by Terry B. Smith
Surveyor's Michigan License No. 25873

Date 12-18-2000