

**SURVEY & REMONUMENTATION**

FEB 11 1998

Liber 00002 Page 0419

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in CENTRAL LAKE TWP.

ANIRIM (County)	Located In:	Corner Code #
1. Public Land Survey SW S 14	T 31N R 8W	I-7
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

ANTRIM COUNTY MI.  
Register of Deeds  
Recorded

12-15-1997 08:50:27

Wanda R. Conway  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

137

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, NEIL L. WAY, in a field survey on 19 NOV., 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
GLO SET HEMLOCK POST, APRIL 1857, SUGAR 18 N54W 6, SUGAR 14 S37E 30

CHURCH (CO. SURVEYOR), JUNE 1907, A STONE WITH A CROSS ON TOP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1/2" FOUND IRON ROD, 0.4' BELOW GRAVEL SURFACE ON EXTENDED CENTERLINE M-88 TO THE SOUTH AND WEST.

FOUND WIT'S AS RECORDED BY L. FEINDT, L. 222 P.218

FOUND WIT'S AS RECORDED BY A. LENNOX, L. 226 P. 798, L.290 P. 1094, L.296 P. 438, L. 316 P.512

FOUND WIT'S AS RECORDED BY G. AVENDT, L. 326 P. 119


FOUND WIT'S AS RECORDED BY S. CHAMBERLAIN, L.295 P. 170

Ratified by Peer  
Group in accordance  
with P.A. 345  
Antrim Co. Chairman

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
And/or L. Lennox  
Nov. 18, 1997

SET ANTRIM COUNTY MONUMENT, 0.5' BELOW GRAVEL SURFACE, ON EXTENDED CENTERLINE M-88 TO THE SOUTH AND WEST

- N 41 W 31.68' SET NAIL, SW/SIDE UTILITY POLE
- N 51 E 36.47' SET NAIL, S/SIDE UTILITY POLE
- S 15 W 74.01' FOUND NAIL & TAG (#21566), E/SIDE POWER POLE
- S 19 E 75.56' SET NAIL, W/SIDE POWER POLE



Signed by Neil L. Way  
Surveyor's Michigan License No. 28432

Date 24 NOV. 1997