

**SURVEY & REMONUMENTATION**

FEB 11 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00002 Page 0431  
ANTRIM COUNTY MI.  
Register of Deeds  
Recorded

For corners in

CENTRAL LAKE

|                                       |                                       |               |
|---------------------------------------|---------------------------------------|---------------|
| <u>ANTRIM</u><br>(County)             | Located In:                           | Corner Code # |
| 1. Public Land Survey E 1/4<br>SEC 23 | T.31N R.8W<br>T. R.<br>T. R.<br>T. R. | K-8           |
| 2. Property Controlling<br>in Section | S. T. R.<br>S. T. R.                  |               |
| 3. Miscellaneous<br>Property in Sec.  | S. T. R.<br>S. T. R.                  |               |

12-22-1997 10:11:27

Wanda R. Conway  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, RICHARD J. KRAL, in a field survey on 8-21-97, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:


**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


|    |   |    |   |    |   |    |   |    |   |    |   |    |   |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
|    | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |

**A. Description of original monument and accessories and/or subsequent restoration:**  
**K-8, 1/4 CORNER COMMON TO SEC. 23 & 24, T31N-R8W**  
 1857, SUBDIVISION OF TWP., RE-SURVEY BY E.D. ATWATER; SET 4" BEECH POST; 7" BEECH, N41°E, 9 LKS (5.94'); 5" BEECH, S52°W, 42 LKS (27.72')  
 1969, SURVEY BY C.E. OSTLING, SHOWS CORNER AS 1/2" X 18" BAR & 2.30' INTO ROW. OF RD. NO ACCESSORIES GIVEN, OTHER THAN A ROW. IRON, WEST, 63.70'  
 1976, SURVEY BY N.B. DEYOUNG, SHOWS CORNER ON DRAWING, NO DESCRIPTION OR ACCESSORIES, OTHER THAN A ROW. IRON, WEST,

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
**K-8, 1/4 CORNER COMMON TO SEC. 23 & 24, T31N-R8W**  
 FD. 1/2" IRON ROD 33' EAST OF CENTERLINE N-S. GR. ROAD PULLED & REPLACED WITH ANTRIM COUNTY MONUMENT (BERNTSEN MODEL G-1[30" PISTON] WITH G-2 CAP).  
 FD. 1/2" IRON ROD ON W. ROW ROAD N83°W, 63.56' (R. 63.70')  
 FD. 1/2" IRON ROD ON E. ROW ROAD S83°E, 2.34' (R. 2.30')

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
**K-8, 1/4 CORNER COMMON TO SEC. 23 & 24, T31N-R8W**  
 FD. 1/2" IRON ROD 33' EAST OF CENTERLINE N-S. GR. ROAD PULLED & REPLACED WITH ANTRIM COUNTY MONUMENT.  
 FD. 1/2" IRON ROD ON W. ROW ROAD N83°W, 63.56' (R. 63.70')  
 FD. 1/2" IRON ROD ON E. ROW ROAD S83°E, 2.34' (R. 2.30')  
 SET NAIL ON SIDE 8" MAPLE, N08°E, 37.42'.  
 SET NAIL ON SIDE BLAZED 7" LOCUST, N80°E, 18.60'.  
 SET NAIL ON SIDE 5" LOCUST, S57°E, 49.50'  
 SET NAIL ON SIDE BLAZED 10" LOCUST, S18°E, 10.77'

Ratified by Peer  
 Group in accordance  
 with P.A. 345  
 Antrim Co. Chairman  
  
 Arthur L. Lennox  
 Nov. 18, 1997



Signed by Richard J. Kral  
 Surveyor's Michigan License No. 26460

Date 12-14-97