

SURVEY & REMONUMENTATION

FEB 11 1998

Liber **00002** Page **0433**

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

ANTRIM COUNTY MI.
Register of Deeds
Recorded

For corners in **SECTION**

CENTRAL LAKE

| | | |
|--|-------------|---------------|
| <u>ANTBIM</u> | Located In: | Corner Code # |
| (County) | | |
| 1. Public Land Survey L 9 T 31N R 8W L-7 | | |
| SEC 24 T R | | |
| T R | | |
| T R | | |
| 2. Property Controlling S T R | | |
| in Section S T R | | |
| 3. Miscellaneous S T R | | |
| Property in Sec. S T R | | |

12-22-1997 10:11:46

Handa R. Conway
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 13 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, RICHARD J. KRAL, in a field survey on 8-20-97, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-7, 1/4 CORNER COMMON TO SEC.'S 13 & 24, T31N-R8W
- 1857, SUBDIVISION OF TWP., RE-SURVEY BY E.D. ATWATER; SET POST 3" BEECH POST; 7" BEECH S3 1/2°E, 20 LKS (13.20'); 11" SUGAR, N36°E, 21 LKS. (13.86')
- 1906, SURVEY BK #1, PG. 256 BY B.L. CAUKIN, DEPT. CO. SURVEYOR; FD STAKE HOLE, FILLED WITH VEGETABLE MOULD WELL DEFINED; SET WHITE STONE WITH CROSS MARKED ON TOP AND BURIED BROKEN GLASS AROUND IT; 10" SUG., N44 1/2°W, 22 1/2 LKS. (14.85')
- 1907, RESURVEY BK #1, PG. 268 BY F.S. CHURCH, CO. SURVEYOR; NO DESCRIPTION OF CORNER; MARKED 11" SUGAR, N80°W, 40.0' (BUT SET WAGON SKEIN AT BOTH 1/8 COR'S E & W OF COR.)
- 1979, SURVEY BY N.B. DEYOUNG. FD 3/4" PIPE; P. POLE, S80°W, 59.35'; 6" MAPLE EAST, 51.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-7, 1/4 CORNER COMMON TO SEC.'S 13 & 24, T31N-R8W
- FD. "T" IRON IN CENTER OF 2 1/4" IRON WAGON SKEIN, 6.5' WEST OF CENTERLINE N-S GR. ROAD OPPOSITE OLD FENCE LINE TO WEST, 35' EAST OF N-S OVERHEAD POWER LINE
- PULLED & REPLACED WITH ANTRIM COUNTY MONUMENT (BERNTSEN MODEL G-1 [30" PISTON] WITH G-2 CAP).
- NO POWER POLE TO WEST OR MAPLE TO EAST PER DEYOUNG SURVEY OF 1979.
- NO G.L.O. WITNESS WERE FOUND.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-7, 1/4 CORNER COMMON TO SEC.'S 13 & 24, T31N-R8W
- FD. "T" IRON IN CENTER OF 2 1/4" IRON WAGON SKEIN, 6.5' WEST OF CENTERLINE N-S GR. ROAD OPPOSITE OLD FENCE LINE TO WEST, 35' EAST OF N-S OVERHEAD POWER LINE
- PULLED & REPLACED WITH ANTRIM COUNTY MONUMENT
- SET NAIL IN SIDE OF 30" MAPLE, N86°W, 100.80'
- SET NAIL IN SIDE OF TRIP. 9" COTTONWOOD, N89°E, 217.65'
- SET NAIL IN W. SIDE P. POLE #CL4-85-10, S14°W, 237.20'
- CENTER OF 8" WATER WELL, S18°W, 225.83'
- SE COR. OF HOUSE FOUNDATION, N33°W, 136.83'

Ratified by Peer
Group in accordance
with P.A. 345
Antrim Co. Chairman

Arthur L. Lennox
Arthur L. Lennox
Nov. 18, 1997



Signed by Richard J. Kral

Date 12-14-97

Surveyor's Michigan License No. 26460