

SURVEY & REMONUMENTATION

FEB 11 1998

Liber 00002 Page 0436

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ANTRIM COUNTY MI.
 Register of Deeds
 Recorded

For corners in

CENTRAL LAKE

<u>ANTRIM</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	SE T.31N R.8W	<u>M-7</u>
	SEC 13 T.31N R.7W	<u>A-7</u>
	T. R.	
	T. R.	
2. Property Controlling in Section	S. T. R.	
	S. T. R.	
3. Miscellaneous Property in Sec.	S. T. R.	
	S. T. R.	

12-22-1997 10:12:15

Manda R. Conway
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, RICHARD J. KRAL, in a field survey on 8-21-97, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
M-7, 1/4 CORNER COMMON TO SEC. 13 & 24, T31N-R8W & A-7, SEC. 18 & 19, T31N-R7W
 1856, RESURVEY TWP. BOUNDARY BY E.D. ATWATER; SET CORNER, 6" BEECH, N51 3/4°E, 71 LKS. (46.86'); 13" SUGAR S50 3/4°E, 43 LKS. (28.38')
 1906, SURVEY BK. #1, PG. 256, BY B.L. CAUKIN DEPT. CO. SURVEYOR; DROVE GAS PIPE 4' LONG.
 1907, RESURVEY BK. 1, PG. 268, BY F.S. CHURCH CO. SURVEYOR, FD A GAS PIPE WITH STAKE ON TH EAST SIDE OF IT.
 1907, SURVEY BK #1, PG. 274, BY F.S. CHURCH CO. SURVEYOR, FD GAS PIPE; NO ACCESSORIES.
 1993, SURVEY REC. IN LIB. 394, PG. 640; BY B.M. JONES, FD 1" PIPE; 18" MAPLE, S66°E, 37.35'; 12" ELM, S41°E, 52.50'; 28" MAPLE, N33°W, 71.54'; 8" ELM, S34°W, 70.90'.
 1994, SURVEY RECORDED IN LIB. 215, PG. 566, BY M.C. FEINDT, FD CORNER, 12" MAPLE S50°E, 37.10'; 25" ELM, N38°E, 73.40'; 14" MAPLE, N40°W, 71.29.
 1994, LCRC. RECORDED, LIB. 2, PG. 197; BY A. LENNOX, CO. SURVEYOR, NO DESCRIPTION OF CORNER, 10" MAPLE, S50°E, 37.20'; 10" MAPLE, S60°E, 47.45' 6" ELM, S30°W, 71.00'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-7, 1/4 CORNER COMMON TO SEC. 13 & 24, T31N-R8W & A-7, SEC. 18 & 19, T31N-R7W
 FD. 5/8" X 36" BENT IRON PIPE OVER A 1" IRON PIPE 36" BELOW RD. SURFACE & 8.5' W. OF C/L N-S GR. ROAD, OPPOSITE GR. DRIVE TO WEST
 PULLED & REPLACED WITH ANTRIM COUNTY MONUMENT (BERNTSEN MODEL G-1 [30" PISTON] WITH G-2 CAP).
 FD. NAIL IN TAG #3920, IN FACE OF 20" MAPLE N30°W, 70.91 (R. 71.54)
 FD IRON & CAP #20357 & 25873 AT ROW ROAD S85°E, 32.87' (R. 33.00')
 FD. SPIKE IN SIDE OF 12" MAPLE S63°E, 37.31' (R. 37.35', 37.10', & 37.20')
 FD. SPIKE IN SIDE OF 9" ASH S38°E, 52.39' (R. 52.50')
 FD. SPIKE IN SIDE OF 9" ELM S40°W, 70.90' (R. 70.90' & 71.00')
 FD. SPIKE IN SIDE OF 13" MAPLE S70°E, 47.5' (R. 47.45')

Witnessed to perpetuate locating the position of the corner:
 T.31N R.7W
 SURFACE & 8.5' W. OF C/L N-S GR. ROAD, OPPOSITE GR.


FD. SPIKE IN SIDE OF 12" MAPLE S63°E, 37.31' (R. 37.35', 37.10', & 37.20')
 FD. SPIKE IN SIDE OF 9" ASH S38°E, 52.39' (R. 52.50')
 FD. SPIKE IN SIDE OF 9" ELM S40°W, 70.90' (R. 70.90' & 71.00')
 FD. TO FACE OF 13" MAPLE (NO NAIL FD.) S70°E, 47.5' (R. 47.45')

Ratified by Peer
 Group in accordance
 with P.A. 345
 Antrim Co. Chairman

Arthur L. Lennox

Arthur L. Lennox
 Nov. '18, 1997

Date 12-14-97



Signed by Richard J. Kral
 Surveyor's Michigan License No. 26460