

AREMONT

COMMISSION

Arenac County Remonumentation

LIBER. 002 PAGE 077

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Arenac (County)	Located In:	Corner Code #
1. Public Land Survey	T18N R 4E	A-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED
JAN 2 11 16 AM '97
AREMAC COUNTY
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael J. MacDonald, in a field survey on July 26, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			1
3													
4	7						8			9			10
5													
6	10						17			16			15
7													
8	19						20			21			22
9													
10	30						29			28			27
11													
12	31						32			33			34
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-6 Post set by L. Clason D.S. in 1837.
County Surveyor G. Turner in 1908 set stake on line and equal distance between A-5 and A-7.
L.C.R.C. - L. 1, P. 325 by T. Lapham - fnd square bolt.
Survey by Norstar in April 1992 - fnd square bolt.

ACCEPTED BY THIS AREMAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT "A" MEETING HELD ON 25 NOV. 1996
Paul M. Ciosek
PAUL M. CIOSEK P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 Fnd 1" square axle shaft 18" long surrounded by stones and 1" x 12" long iron bar below axle shaft.

Recorded Witnesses as follows:
N 60° W 27.8' to center of vertical RR tie (28.24' - R)
N 35° W 42.75' to N end 36" culvert (Rec to S inv.)
S 8.1' to centerline ditch extended.
Also fnd 1/2" iron 28.52' N of axle shaft. (See survey L. 1, P. 325)
Monument accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 Replaced axle shaft with 5/8" x 24" long rebar and Arenac County Remonumentation cap.
N 28°30' W 122.49' to nail and tag in SW face of pole.
S 84°30' W 137.15' to nail and tag in S face of 12" Elm on S bank of ditch.
S 05°30' E 155.68' to filed notch in E end of 36" CMP.
N 51° E 44.20' to nail and tag in NW cor of vertical RR tie.
N 28.52' to 1/2" iron rod in road.



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 19 Dec 96