

1837

### Arenac County Remonumentation

#### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 002 PAGE 079

For corners in

<u>Arenac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18</u> N R <u>4E</u>	<u>A-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Michael J. MacDonald, in a field survey on October 10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	13		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-8 Post set by L. Clason D.S. in 1837 at 40 chains from A-9 and A-7. County Surveyor or C. Thornthwaite in 1911 find one original witness tree and set a cedar post on line and equal distances from A-9 and A-7.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8 No monument found. Set on line and equal distance from A-9 and A-7 and is accepted as a careful and faithful re-establishment of the position of the original corner.

REC'D  
 ARENAC COUNTY  
 REGISTER OF DEEDS  
 JAN 2 11 14 AM '97  
 RECORDED

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 25 Nov. 1996  
*Paul M. Ciosek*  
 PAUL M. CIOSEK P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 Set 5/8" x 3/8" rebar with Arenac County Remonumentation cap approximately 8" below surface and surrounded with rocks.

E 28± to N-S crop line.  
 N 30°30' E 59.38' to nail and tag in W face of 12" Elm.  
 S 05°30' E 323.62' to nail and tag in W face of corner fence post.  
 S 20°30' E 315.55' to nail and tag in E face of 10" Ash 6' above ground.  
 N 49° E 52.17' to centerline of plug in vertical irrigation pipe.



Signed by Michael J. MacDonald  
 Surveyor's Michigan License No. 22438

Date 19 Dec 96