

Arenac County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Arenac	Located in:	Corner Code #
(County)		
1. Public Land Survey	T <u>18</u> R <u>4E</u>	<u>B-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

LIBER **002** PAGE **080**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael J. MacDonald, in a field survey on August 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-5 Post set by J. Burt in 1843.
Survey by Norstar in April 1992 (no corner set).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5 No monument found.
Set corner at proportionate distances on line between A-5 and C-5. Alignment of E-W line agrees more or less with data on Norstar survey but is approximately 14.5' E of a position calculated from said survey. Corner of fence N and E is 6.5' E and 11.8' N of proportioned position of B-5. Monument is accepted as a careful and faithful reestablishment of the position of the original corner.

ARENAC COUNTY REGISTER OF DEEDS
 JAN 2 11 14 AM '97
 RECORDED

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 25 Nov. 1996
Paul M. Glosex
 PAUL M. GLOSEX P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5 Set 5/8" x 24" rerod with Arenac County Remonumentation cap 6" below ground and surrounded with rocks.

N 61° E 52.42' to nail and tag in 10" Beech.
N 27°45' E 13.80' to nail and tag in W side of corner fence post.
N 69°20' W 41.23' to nail and tag in S face of 24" base of triple Ash.
S 05°10' E 22.20' to nail and tag in W face of 12" Ash.



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 19 Dec 96