

COMMISSION

Arenac County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 002 PAGE 081

For corners in

Arenac
(County)

Located In: Corner Code #

- 1. Public Land Survey T18N R 4E B-7
- T R
- T R
- T R
- 2. Property Controlling in Section S T R
- S T R
- 3. Miscellaneous Property in Sec. S T R
- S T R

RECORDED

JAN 2 11 24 AM '97

ARENAC COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Michael J. MacDonald, in a field survey on July 26, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-7 Post set by J. Burt in 1843.
Survey by Norstar in April 1992 (no corner set).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7 No monument found.
Set corner at proportionate distances and on line between A-7 and C-7 and is accepted as a careful and faithful re-establishment of the position of the original corner.

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 25 Nov. 1996
Paul M. Ciosek
PAUL M. CIOSEK P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7 Set 5/8" x 24" rerod with Arenac County Remonumentation cap
2'± S of E-W fence and 33'± W of fence corner.

S 85° E 33.80' to nail in corner fence post.
S 82° W 23.60' to nail in 12" Maple.
S 32° E 57.74' to nail in 5" Birch.
S 77° E 50.03' to nail in 8" Maple.



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 19 Dec 96