

Arenac County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **002** PAGE **082**

For corners in

<u>Arenac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T18N R 4E</u>	<u>C-5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael J. MacDonald, in a field survey on July 26, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-5 Post set by J. Burt in 1843.
Recorded Survey: L. 1, P. 450-453 (no call).
Recorded MDOT Witness Card: L. 1, P. 198, fnd T-iron.

RECORDED
JAN 2 11 14 AM '97
ARENAC COUNTY
REGISTER OF DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5 Fnd T-iron 15" long also fnd 1" steel pin 2.1' below surface 0.2' W of T-iron.

Calc 5255.78' (5255.79' MDOT) to E-5.
Meas 2624.49' (2624.37' MDOT) to C-6.

No remaining witnesses from MDOT card.
T-iron accepted as best available evidence of the position of the original corner.

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 25 Nov. 1996
Paul M. Ciosek
PAUL M. CIOSEK P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5 Removed T-iron and set 5/8" x 24" long rerod with Arenac County Remonumentation cap in monument box.

S 50° W 47.13' to nail and tag in SE face of 6" cedar post.
N 84° W 32.32' to nail and tag in S face of 6" cedar post.
S 02° E 82.65' set 3/8" re-rod with cap #18999.
S 09° E 433.83' to nail and tag in W face of 40" Maple cluster.
1.5' E of centerline of pavement.



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 18 Dec 96