

Arenac County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Arenac
(County)

Located In:

Corner Code #

1. Public Land Survey

T18N R 4E

C-6

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

LIBER 002 PAGE 083
JAN 2 11 14 AM '97
RECORDED
ARENAC COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael J. MacDonald, in a field survey on July 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 19 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

C-6 Post set by J. Burt in 1843.

MDOT Witness Card: L. 1, P. 202 - found RR spike (1963).
Survey by R. Higgins: L. 1, P. 452 - no call.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6 Fnd RR spike 0.3' below surface - also fnd 2" x 3" piece of magnetic slag 12" below RR spike.

2624.49' meas to C-5 (2624.37' MDOT).
2630.06' meas to C-7 (2629.98' MDOT).
Angle meas 179°18'31" C5-C6-C7 (179°18'29" MDOT).
Monument accepted as the best available evidence of the position of the original corner.

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1890 AT 'A' MEETING HELD ON 25 Nov. 1996
Paul M. Dosek
PAUL M. DOSEK P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6 Replaced RR spike with 5/8" x 24" long rebar with Arenac County Remonumentation cap in mon box.

N 36° E 93.50' to nail and tag in W face of 14" Maple.
N 15° W 126.72' to nail and tag in SW face of pole.
S 82° E 38.55' to nail and tag in N face of 4" Red Pine.
S 05° E 86.43' to set 3/8" rebar with cap #18999.



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 19 Dec 96