

Arenac County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Arenac
(County)

Located In:

Corner Code #

1. Public Land Survey

T 18N R 4E C-7
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER 002 PAGE 084

Register of Deeds Stamp & File Number

I, Michael J. MacDonald, in a field survey on July 23, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-7 Post set by J. Burt in 1843.

MDOT Witness Card: L. 1, P. 203 - fnd 2" pipe and raised with 5/8" rebar (1963).

L.C.R.C.: L. 1, P. 94 - by H. Fiharty - fnd 1" Iron bar (1976) - survey recorded in wrong township.

Survey by Fiharty - L. 1, P. 288 - fnd 1" bar (1976) - wrong location.
Survey by R. Higgins - L. 1, P. 453 - no call.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 Fnd 5/8" rebar 18" long near surface set in 2 1/2" pipe 1.6' below surface.

5286.68' meas to E-7 (5286.74' MDOT).
2630.08' meas to C-6 (2629.98' MDOT).
2625.97' meas to C-8 (2625.84' MDOT).
Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Set Arenac County Remonumentation cap on existing Iron - set mon box.

N 80° W 30.89' to nail and tag in S face of Twin 26" Willow.
S 48° W 48.53' to nail and tag in NW face of pole.
S 27° E 64.37' to nail and tag in NE face of pole.
N 57° E 26.58' to set 3/8" Iron and cap #18999.

Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 19 Dec 96

RECORDED
JAN 2 11 1st AM '97
ARENAC COUNTY
REGISTER OF DEEDS

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 25 Nov. 1996
Paul M. Croser
PAUL M. CROSER P.S., CHAIRMAN

