

COMMISSION

Arenac County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 002 PAGE 086

For corners in

Arenac	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>18</u> N R <u>4E</u>	<u>D-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, Michael J. MacDonald, in a field survey on July 26, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-5 Post set by J. Burt in 1843.

MDOT Witness Cards - L. 1, P. 200 and 201 - set 5/8" iron bar in fence corner recognized by local land owners as 1/4 cor. Survey by R. Higgins - L. 1, P. 452 - no call.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 No monument fnd, reset per MDOT courses between C-5 and E-5.

2631.29' calc and per MDOT to E-5.
2624.49' calc to C-5 (2624.50' MDOT).

Location is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 Set 5/8" x 24" long rebar with Arenac County Remonumentation cap 6" below surface of black top shoulder.

W 2.3' to E edge of S-bound lands.
E 167.6' to W edge of N-bound lanes.
N 41° E 88.54' to nail in 8" Maple.
S 42°20' W 38.43' to W edge of S-bound lanes at sta 2406+00.
Mon at sta 2406+28± (2406+27.96 per MDOT).

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 25 Nov. 1996
Paul M. Ciosek
PAUL M. CIOSEK P.S., CHAIRMAN

RECORDED
JAN 2 11 15 AM '97
ARENAC COUNTY REGISTER OF DEEDS



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 19 Dec 96