

COMMISSION

Arenac County Remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **002** PAGE **088**

For corners in

<u>Arenac</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>18</u> N R <u>4</u> E	<u>E-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael J. MacDonald, in a field survey on July 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-5 Post set by J. Burt in 1843.
MDOT Witness Card - L. 1, P. 200, fnd 3/4" pipe (1963).
Survey by R. Higgins, L. 1, P. 450, fnd 3/4" Iron (1981).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5 Fnd 1" O.D. pipe 30" long set in wood post with ring of stones around post. Post 12" below road surface.
Meas 2630.74' to E-6 (2630.37' - MDOT).
Recorded Witnesses - NE 79.92' Rec - meas to centerline pole 10' W of centerline road (7' - R).
Monument accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5 Set 5/8" x 24" long rebar with Arenac County Remonumentation cap. Left ring of stones in place.
S 25° W 96.34' to nail and tag in E face of 22" Maple.
S 10° E 186.17' to nail and tag in W face of pole.
N 45° E 79.90' to nail and tag in W face of pole.
N 25° W 139.03' to nail and tag in E face of SE door column in barn.
S 60° W 185.70' to NW cor of brick garage at Hse #4012.

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT "A" MEETING HELD ON 25 Nov. 1996
Paul M. Gosek
PAUL M. GOSEK P.S., CHAIRMAN

ARENAC COUNTY
REGISTER OF DEEDS
RECORDED
JAN 2 11 15 AM '97



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 12 Dec 96