

COMMISSION

Arenac County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 002 PAGE 089

JAN 2 11 15 AM '97

ARENAC COUNTY
REGISTER OF DEEDS

RECORDED

For corners in

Arenac
(County)

Located In:

Corner Code #

1. Public Land Survey

T18N R 4E E-6

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael J. MacDonald, in a field survey on July 19, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-6 Post set by J. Burt in 1843.

MDOT Witness Card - L. 1, P. 202, fnd 1 1/2" Iron (1963).
Survey by R. Higgins, L. 1, P. 451, fnd 1 1/4" Iron (1981).
Survey by J. Meyers, L. 1, P. 524, fnd 1 1/2" Iron (1985).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 Fnd 1 1/2" x 39" long steel axle also remnants of wood 18" below road surface.
Recorded Witnesses - Rec to tree - meas okay to centerline tree.
S 85° W 30.04' to 23" (20" - R) Maple.
S 30° W 74.51' to 21" (18" - R) Maple.
S 85° E 88.62' to 32" dead tree (R - 25" Oak).
Monument accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 Replaced axle with 5/8" x 24" long rebar with Arenac County Remonumentation cap.

S 85° W 132.24' to NE cor of block fndtn of Hse #4260.
W 29.94' to nail and tag in N face of 21" Maple.
S 30° W 74.38' to nail and tag in SE face of 17" Maple.
S 70° E 36.38' to nail and tag in N face of 14" Elm.
S 20° E 126.02' to nail and tag in W face of pole with transformer.

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 25 NOV. 1996
Paul M. Ciosek P.S., CHAIRMAN



Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438

Date 19 Dec 96