

Arenac County Remonumentation

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 002 PAGE 090

For corners in

Arenac (County)	Located In:	Corner Code #
1. Public Land Survey	T18N R 4E	E-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

ARENAC COUNTY
REGISTER OF DEEDS
 JAN 2 11 15 AM '97
 RECORDED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael J. MacDonald, in a field survey on July 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-7 Post set by J. Burt in 1843.

MDOT Witness Card - L. 1, P. 201, fnd 5/8" bolt with 1" square head (1963).

Recorded Surveys - L. 1, P. 451, R. Higgins fnd 3/4" iron (1981).
 L. 1, P. 524, J. Meyers fnd 5/8" bolt (1985).
 L. 1, P. 519, J. Meyers fnd 5/8" bolt (1985).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 Fnd 5/8 x 10" long bolt with square head also fnd boat spike 8.0' E of bolt.

Meas 5286.74' to C-7 (5286.68' - MDOT).
 Meas angle 88°55'16" C7-E7-E6 (88°55'22" - MDOT).
Recorded Witness - N 45° W 42.76' to face of road sign post.
 Bolt accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 Replaced 5/8" x 10" bolt with 5/8" x 24" rebar with Arenac County Remonumentation cap.

S 85° E 8.0' to boat spike in road.
 N 46° W 49.10' to nail and tag in SW face of pole.
 N 45° W 42.80' to face of 2" steel post 6' tall.
 S 60° E 94.04' to nail and tag in NE face of 3" Cedar.
 S 20° W 115.37' to nail and tag in E face of 18" Elm.

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT "A" MEETING HELD ON 25 NOV. 1996
Paul M. Gioser
 PAUL M. GIOSER P.S., CHAIRMAN



Signed by Michael J. MacDonald
 Surveyor's Michigan License No. 22438

Date 19 Dec 96