

APR 06 1999

**ARENAC COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

ARENAC  
(County)

Located In: \_\_\_\_\_

Corner Code F-7

1. Public Land Survey T 18N R 4E  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Page 1 of 1  
ROSE SMITH  
ARENAC CO. REG. OF DEEDS  
RS Rec. Date 12/29/98 Time 10:51  
RECORDING FEES: 2/ 180 1P 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, DALE L. WINIECKE, in a field survey on July 29, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- F-7
1. ORIGINAL POST SET IN JULY 1843 BY J. BURT, D.S.  
CEDAR 9", N 73°W 13 LINKS  
CEDAR 13", S 64°E 15 LINKS
  2. LCRC, L. 1, P. 205, N. CALDWELL, PS#12106, (1964), FOUND 3/4" PIPE
  3. CERTIFICATE OF SURVEY, L. 2, P. 48-49, W. RUDELL, PS#14769, (1993), FOUND 3/4" PIPE, NO WITNESSES
  4. LCRC, L.1, P.331, W. RUDELL, PS# 14769, (1993), FOUND 3/4" PIPE

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

F-7  
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND A 3/4" PIPE AT THE GRAVEL ROAD SURFACE. EXCAVATED THE AREA UNDER THE PIPE AND FOUND NO OTHER OBJECTS.  
CHECKED MSHD WITNESSES FROM L.1, P.205, S54°W TO POWER POLE 70.56' (R) 70.65' (M)  
THE 3/4" PIPE WAS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

F-7  
REPLACED 3/4" PIPE WITH 5/8" X 24" LONG REBAR WITH ARENAC COUNTY REMONUMENTATION CAP.  
NORTH 276.23' TO SET NAIL AND TAG IN EAST FACE OF POWER POLE  
S 04°E 75.33' TO SET NAIL AND TAG IN WEST FACE OF TWIN 20" POPLAR  
S 60°E 93.13' TO SET NAIL AND TAG IN SW FACE OF 24" POPLAR  
SOUTH 21.20' TO CENTERLINE OF EAST LEG OF ARROW SIGN  
S54°W 70.65' TO POWER POLE 70.56' (R)



Signed by Dale Winiecke  
Surveyor's Michigan License No. 41915

Date 12/28/98

FB. 2, P. 66

ACCEPTED BY THIS ARENAC COUNTY SURVEY REG. GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10 NOV 1998  
Paul M. Glose  
PAUL M. GLOSE, P.S., CHAIRMAN